BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Comprehensive Development of Hegdenagar East Side cross roads and Shabarinagar cross road in Ward No.06

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. V CHANDRAPPA	
				In figures	In words
1	531.72	Removing and resetting of footpath slab	Sqm	219.18	Rupees Two Hundred Nineteen And Paise Eighteen Only
2	202.00	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. ii) Dismantling brick/Tile work B. In cement mortar	Cum	390.51	Rupees Three Hundred Ninety And Paise Fifty One Only
3	54.05	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. iii) Dismantling Stone Masonry.B. Rubble stone masonry in cement mortar	Cum	390.51	Rupees Three Hundred Ninety And Paise Fifty One Only
4	160.50	Removing and resetting of kerb stones	m	110.15	Rupees One Hundred Ten And Paise Fifteen Only
5	1771.08	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3	Cum	144.63	Rupees One Hundred Forty Four And Paise Sixty Three Only
6	263.63	KSRRB M2100-10: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM of machinery, curing, formworks, scaffolding and centering complete as per specifications	Cum	5690.83	Rupees Five Thousand Six Hundred Ninety And Paise Eighty Three Only
7	807.23	Providing laying palin / reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300kgs with 20mm and downsize granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering shuttering cost of materials, HOM of machinery, curing etc., complet excluding cost of steel as per MORTH specification No. 1500,1700,2200 including cost of materials, labour, HOM complete as per specifications wall & bottom thickness 15cm	Cum	7420.88	Rupees Seven Thousand Four Hundred Twenty And Paise Eighty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. V CHANDRAPPA	
				In figures	In words
8	97.60	Providing and laying in position plain/reainforced cement concrete M20 for sub structure/ Superstructure works, with cement @ 320 kgs, 20 mm & down size graded granite metal coarse aggregate @ 0.69 cum and fine aggregates @ 0.46 cum machine mixed with superplasticisers @ 3ltrs confirming to IS 9103-2008, concrete laid in layers, well compacted and providing weep holes wherever necessary with necessary scaffoldingf, formwork etc., including cost of labour, HOM curing etc., complete	Cum	5539.52	Rupees Five Thousand Five Hundred Thirty Nine And Paise Fifty Two Only
9	57.23	KSRRB M2200-6. Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH specification No 1600 & 2200	MT	75914.40	Rupees Seventy Five Thousand Nine Hundred Fourteen And Paise Forty Only
10	1663.20	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	2398.34	Rupees Two Thousand Three Hundred Ninety Eight And Paise Thirty Four Only
11	27.72	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5632.15	Rupees Five Thousand Six Hundred Thirty Two And Paise Fifteen Only
12	1.70	Wrought iron and mild steel welded work KSRRB M300-18. Wrought iron and mild steel welded work (using angles, square bars, tees and channel grills, grating frames, gates and tree guards of any size and design etc. including cost of screens and welding rods or bolts and nuts complete fixed in position but without the cost of excavation and concrete for fixing which will be paid separately complete as per specifications.	Qtl	7996.08	Rupees Seven Thousand Nine Hundred Ninety Six And Paise Eight Only
13	1604.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete	Nos	453.93	Rupees Four Hundred Fifty Three And Paise Ninety Three Only
14	73.42	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	6032.39	Rupees Six Thousand Thirty Two And Paise Thirty Nine Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. V CHANDRAPPA	
				In figures	In words
15	577.10	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8	Sqm	89.01	Rupees Eighty Nine And Paise One Only
16	1771.08	KSRRB M100-4.1: Cost of Haulage including loading and unloading of stone Boulder / Stone aggregates / Sand /Kankar / Moorum KSRRB M100-1: Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip including with all lead and lifts, loading and unloading,tools, plants, HOM of machinery, cost of materials, labour and other incidental charges etc., complete as per specification and as per the direction by Engineer in charge of the work.MORTH Chapter 1	Cum	86.70	Rupees Eighty Six And Paise Seventy Only
17		GST @ 12%			

Contractor

Executive Engineer
Project Division
Yelahanka Zone